

# HALE

## TRAILER

### BRAKE & WHEEL



**A026275-A026276**  
**VIN: 00127 & 00126**

#### SALES | RENTALS | PARTS | SERVICE

<b>Allentown, PA:</b>	<b>800-383-8894</b>	<b>Little Rock, AR:</b>	<b>833-424-8944</b>
<b>Baltimore, MD:</b>	<b>888-601-7500</b>	<b>Portland, ME:</b>	<b>800-325-4253</b>
<b>Concord, NC:</b>	<b>800-438-2250</b>	<b>Raleigh, NC:</b>	<b>833-418-9777</b>
<b>Delmar, DE:</b>	<b>866-486-1400</b>	<b>Scranton, PA:</b>	<b>800-569-1400</b>
<b>Des Moines, IA:</b>	<b>888-673-5011</b>	<b>Springfield, MA:</b>	<b>800-854-5306</b>
<b>Elkton, MD:</b>	<b>800-544-7127</b>	<b>Voorhees, NJ:</b>	<b>866-315-0235</b>
<b>Jacksonville, FL:</b>	<b>800-828-3055</b>	<b>Walpole, MA:</b>	<b>800-854-5310</b>

haletrailer.com | @haletrailer     

**800-232-6535** \*FINANCING AVAILABLE

**Base Weight:** 18,540

## 53ET3XP 53 ft. Tridem Paving & Recovery

### TRAILER

<b>Overall Length</b>	53 ft.
<b>Overall Width</b>	102 in.
<b>Weight lbs +/- 2%</b>	19759, including options
<b>Spacing</b>	*NPO*: King pin to center of rear axle not to exceed 42 ft 11 in.

### GOOSENECK

<b>Coupler</b>	Weld in King Pin
<b>Coupler Plate</b>	5/16 in. Hi-Tensile, 48 in. Height
<b>Coupler Location</b>	18 in.
<b>Length</b>	10 ft. 6 in.
<b>Cross Members</b>	Hi-Tensile 4 in. Jr. I-beam @ 16 in. O/C
<b>Swing Clearance</b>	83 in.
<b>Floor</b>	1 1/8 in. Shiplapped Apitong/Keruing
<b>Web</b>	1/4 in. Hi-Tensile

### DECK

<b>Deck Length</b>	35 ft. 1 in.
<b>Loaded Deck Height</b>	35 in.
<b>Main Frame</b>	3/8 in. x 5 in. Top Flange and 1/2 in. x 5 in. Bottom 100 KSI
<b>Cross Members</b>	Hi-Tensile Standard 4 in. I-beam @ 12 in. O/C on Lower Deck w/ Knee Braces
<b>Side Rail</b>	6 in. @ 8.2 Channel
<b>Web</b>	3/16 in. Hi-Tensile
<b>Landing Gear</b>	Dual 2 Speed
<b>Floor</b>	1 3/8 in. Shiplapped Apitong/Keruing with 3/16 in. Deckplate over the wheels
<b>In Floor Chain Box</b>	1 - located at rear of Gooseneck, 1 - located at rear of main deck, with deckplate covers included

### SUSPENSION/AXLES

<b>Axles</b>	25,000 lbs Capacity
<b>Air Lift</b>	Air Lift c/w Control Box: lead axle
<b>Spread</b>	*NPO*: 60 in.
<b>Suspension</b>	Ridewell RAR 260 U/S 6 1/2 in. Air Ride 25,000 lbs - includes air gauge and dump valve in enclosure
<b>Brakes</b>	Quick Change 12 1/4 in. x 7 in.
<b>Brake Chamber</b>	#3030, All Axles
<b>Air Brake System</b>	2S/1M
<b>Air Tank(s)</b>	Aluminum
<b>Slack Adjusters</b>	Automatic
<b>Camshafts</b>	28 Spline Non Enclosed
<b>Hubs &amp; Drums</b>	8 Stud Unimount C / W Cast Drums
<b>Tires</b>	Tire Upgrade to 245/70R17.5 Continental HTL2 ECO
<b>Tire Inflation</b>	*NPO*: Meritor System, Included
<b>Wheels</b>	Alum. Wheel Pkg. 17.5 (6 steel, 6 polished)

<b>BEAVERTAIL</b>		
	<b>Length</b>	6 ft. @ 8 degree slope, Planked
<b>RAMPS</b>		
	<b>Rear</b>	45 in X 11 ft. Air Operated Bi Fold - Planked
	<b>Main Deck to G/N</b>	12 ft. Inset Full width Air Operated - Planked
	<b>Main Deck to G/N</b>	*NPO*: Ramp Prop Access Covers
<b>GENERAL SPECIFICATIONS</b>		
	<b>Electrical System</b>	Modular, Vapor Proof GROTE Ultra Blue
	<b>Lights</b>	LED CMVSS 108 / FMVSS 108
	<b>Front Connector</b>	SAE J560 7 Pin
	<b>Rear Connector</b>	4 Pin Plug
	<b>Finishing</b>	Preparation by Steel Shot Blast, Commercial / Industrial Topcoat, Oven Baked
	<b>Color</b>	Black
	<b>Mudflaps</b>	1 set of BWS at rear
	<b>Load Securement</b>	* Moulded Rub Rail, Stake Pockets and Spools 24 in. OC
	<b>Load Securement</b>	15, Pair of in Floor Flush Mounted D-Rings: 3 pr GNK; 2 pr B/T; start directly aftr front ramp - 10 pr main deck, evenly spaced