

A027519-A027523 VIN: 178538-178542

SALES | RENTALS | PARTS | SERVICE

Allentown, PA: 800-383-8894 Little Rock, AR: 833-424-8944 Baltimore, MD: 888-601-7500 Portland, ME: 800-325-4253 Concord, NC: 800-438-2250 Raleigh, NC 833-418-9777 Delmar, DE: 866-486-1400 Scranton, PA: 800-569-1400 Des Moines, IA: 888-673-5011 Springfield, MA: 800-854-5306 Elkton, MD: 800-544-7127 Voorhees, NJ: 866-315-0235 Jacksonville, FL: 800-828-3055 Walpole, MA: 800-854-5310

haletrailer.com | @haletrailer f 🕑 🛅 🎯 🛗

800-232-6535

*FINANCING AVAILABLE



Product Hauled: Milk

Barrel Description

Model SRJ3 6250-1 T304, Stainless steel, Round, Jacketed, 3-A

sanitary trailer

Code 3A Sanitary

Capacity 6250 gallons (shell full)

Compartments One Shape Round

Shell Material T304 Stainless steel, #4 finish, 12 gauge barrel. Two piece

barrel with one circumferential weld.

Head Material T304 Stainless steel, #4 finish, 12 gauge

Operating Pressure Atmospheric

Design Temperature 212 Degrees F. (TEMPERATURE RATING OF 212 DEGREE

F. WITH STANDARD INSULATION. THE USE OF OTHER

INSULATIONS MAY DECREASE THE MAXIMUM TEMPERATURE RATING FOR THIS TRAILER. SEE INSULATION FOR MAXIMUM TEMPERATURE RATING

CHANGE.)

Overall Length 42' 6"

Product Various; to be compatible with the materials of construction.

Other Barrel Information

Heat None
Plumbing None
Intransit None
Weld finish W-5 inside

Construction

Rings Stainless steel channel

Longerons 12 gauge Stainless steel channel

Frame Stainless steel, modified angle.

Dam	None	
Dam Drains	None	
Overturn Protection	None	
Cleanout overturns	None	
Manhole	Polar 19" stainless steel lid with dust cover, 4 hold-down. Stainless steel sanitary deck around manhole with dust cover vent under hinge.	
Gasket	Black gasket in cover	
Insulation	3/4" Polyurethane under 3" Polystyrene, R 18.5, 212 DEG F. max	
Thermometer	None	
Jacketing	22 gauge stainless steel bright finish	
Jacket heads	18 gauge stainless steel #3 finish jacket heads.	
* Underlayment	Aluminum .090" underlayment, 24" wide x full length	
Static cable	No static cables installed.	
Hose Carriers		
* Hose Carrier	Aluminum tube 8" diameter x 21' long	
* Hose Carrier	8" aluminum door, at rear	
* Carrier Location	Mounted curbside rear	
Lights and Wiring		
Lig	hts and Wiring	
Lights	12-volt, Truck-Lite grommet mount LED lamp system complying to FMVSS. Combination center marker / turn signals, one each side.	
	12-volt, Truck-Lite grommet mount LED lamp system complying to FMVSS. Combination center marker / turn	
Lights	12-volt, Truck-Lite grommet mount LED lamp system complying to FMVSS. Combination center marker / turn signals, one each side.	
Lights Wiring	12-volt, Truck-Lite grommet mount LED lamp system complying to FMVSS. Combination center marker / turn signals, one each side. Plug-in style harness system.	
Lights Wiring Rear Lights	12-volt, Truck-Lite grommet mount LED lamp system complying to FMVSS. Combination center marker / turn signals, one each side. Plug-in style harness system. Enclosed in stainless steel light boxes	
Lights Wiring Rear Lights Nose box Gladhands	12-volt, Truck-Lite grommet mount LED lamp system complying to FMVSS. Combination center marker / turn signals, one each side. Plug-in style harness system. Enclosed in stainless steel light boxes Standard 7 way, J560 receptacle without circuit breakers.	
Lights Wiring Rear Lights Nose box Gladhands	12-volt, Truck-Lite grommet mount LED lamp system complying to FMVSS. Combination center marker / turn signals, one each side. Plug-in style harness system. Enclosed in stainless steel light boxes Standard 7 way, J560 receptacle without circuit breakers. Gladhand, Phillips, Quick Release	
Lights Wiring Rear Lights Nose box Gladhands	12-volt, Truck-Lite grommet mount LED lamp system complying to FMVSS. Combination center marker / turn signals, one each side. Plug-in style harness system. Enclosed in stainless steel light boxes Standard 7 way, J560 receptacle without circuit breakers. Gladhand, Phillips, Quick Release	
Lights Wiring Rear Lights Nose box Gladhands Upper 5th Wheel	12-volt, Truck-Lite grommet mount LED lamp system complying to FMVSS. Combination center marker / turn signals, one each side. Plug-in style harness system. Enclosed in stainless steel light boxes Standard 7 way, J560 receptacle without circuit breakers. Gladhand, Phillips, Quick Release Indercarriage 5/16" Standard duty upper coupler with Heavy duty double hubbed kingpin.	
Lights Wiring Rear Lights Nose box Gladhands Upper 5th Wheel Paint	12-volt, Truck-Lite grommet mount LED lamp system complying to FMVSS. Combination center marker / turn signals, one each side. Plug-in style harness system. Enclosed in stainless steel light boxes Standard 7 way, J560 receptacle without circuit breakers. Gladhand, Phillips, Quick Release Indercarriage 5/16" Standard duty upper coupler with Heavy duty double hubbed kingpin. Fifth wheel plate painted black. Jost A440, 2-speed, load bearing, telescopic, with swivel type	
Lights Wiring Rear Lights Nose box Gladhands Upper 5th Wheel Paint Landing Gear	12-volt, Truck-Lite grommet mount LED lamp system complying to FMVSS. Combination center marker / turn signals, one each side. Plug-in style harness system. Enclosed in stainless steel light boxes Standard 7 way, J560 receptacle without circuit breakers. Gladhand, Phillips, Quick Release Indercarriage 5/16" Standard duty upper coupler with Heavy duty double hubbed kingpin. Fifth wheel plate painted black. Jost A440, 2-speed, load bearing, telescopic, with swivel type sand shoe. Additional stainless steel bracing mounted to the front of the	
Lights Wiring Rear Lights Nose box Gladhands Upper 5th Wheel Paint Landing Gear * Landing Gear	12-volt, Truck-Lite grommet mount LED lamp system complying to FMVSS. Combination center marker / turn signals, one each side. Plug-in style harness system. Enclosed in stainless steel light boxes Standard 7 way, J560 receptacle without circuit breakers. Gladhand, Phillips, Quick Release Indercarriage 5/16" Standard duty upper coupler with Heavy duty double hubbed kingpin. Fifth wheel plate painted black. Jost A440, 2-speed, load bearing, telescopic, with swivel type sand shoe. Additional stainless steel bracing mounted to the front of the support legs.	
Lights Wiring Rear Lights Nose box Gladhands Upper 5th Wheel Paint Landing Gear * Landing Gear Frame	12-volt, Truck-Lite grommet mount LED lamp system complying to FMVSS. Combination center marker / turn signals, one each side. Plug-in style harness system. Enclosed in stainless steel light boxes Standard 7 way, J560 receptacle without circuit breakers. Gladhand, Phillips, Quick Release Indercarriage 5/16" Standard duty upper coupler with Heavy duty double hubbed kingpin. Fifth wheel plate painted black. Jost A440, 2-speed, load bearing, telescopic, with swivel type sand shoe. Additional stainless steel bracing mounted to the front of the support legs. Stainless steel construction	
Lights Wiring Rear Lights Nose box Gladhands Upper 5th Wheel Paint Landing Gear * Landing Gear Frame Bracing	12-volt, Truck-Lite grommet mount LED lamp system complying to FMVSS. Combination center marker / turn signals, one each side. Plug-in style harness system. Enclosed in stainless steel light boxes Standard 7 way, J560 receptacle without circuit breakers. Gladhand, Phillips, Quick Release Indercarriage 5/16" Standard duty upper coupler with Heavy duty double hubbed kingpin. Fifth wheel plate painted black. Jost A440, 2-speed, load bearing, telescopic, with swivel type sand shoe. Additional stainless steel bracing mounted to the front of the support legs. Stainless steel construction Stainless steel, with cross brace.	

* Suspension

Hendrickson INTRAAX AANT/AANL 23K two axle suspension set, (1) AANT23K fixed and (1) AANL23K lift suspension. Includes 5.75 integrated axles. Axle spacing to be determined by scale.

* Suspension

3/16" Stainless steel subframe extended to the rear 12"

Dump valve

Hendrickson AK-54 automatic dump valve. System exhausts the air from the air bags when the glad-hands are disconnected or when the parking brake is activated and automatically refills when glad-hands are reconnected.

Lift Axle Control

Meritor Lift Axle Control paired with Wabco RSS ECU. Auto load sensor raises and lowers lift axle when loading or unloading, includes manual over-ride. FRONT AXLE TO LIFT AS STANDARD. UNLESS OTHERWISE SPECIFIED.

Hangers

Stainless Steel weld on hangers with soft coat applied to axle and trailing arm.

Subframe

3/16" Stainless steel subframe, 38" wide with stainless fender

supports.

* Bumper

Stainless underride protection. Compliant with both FMVSS and CMVSS, including certification label as required.

Beam

Straight axle beam

Track
Hub & drums

Axle track, 71.5"

Hendrickson 5 year warranty, Ready to roll with Duralite hubs, cast drums and semi-fliud grease. OEM slack adjusters, seals, brake chambers and brake lining.

Anti-lock / Roll stability

OEM Standard 4S/2M with tandem axle roll stability for air-ride suspension.

Air system

One (1) aluminum tank system. 2850 cu. in. meeting FMVSS 121 D.O.T. specifications.

Emission Compliance

NA

Wheels

Tires

Original Equipment Manufacturer, 22.5 X 8.25 Aluminum

polished wheels

* Tire pressure system

Original Equipment Manufacturer, 11R-22.5, Load Range G 14 Ply.

The pressure system

Axle prep for Hendrickson TIREMAAX Pro or TANK Ai tire inflation systems.

Front

Aluminum, single contour, ribbed, front fender, each side.

Rear

Aluminum, double contour, ribbed, rear fender, each side.

Mud flaps

White, anti-sail and anti-spray with Polar logo, mounted front and rear.

Valving and Piping

* Seal provisions

Seal provisions on all openings

Sump

3" stainless steel sanitary drain with mounting ring in rear head.

Discharge location

Rear of trailer.

Outlet valve

3" stainless steel 60TTF valve with aluminum dust cover, attached to mounting ring.

* CIP system * CIP system Short provision for 1 1/2" top mount customer mounted CIP system. 1 1/2" mounting brackets installed for a top mount customer mounted CIP system. 1 1/2" mounting brackets installed for a top mount customer installed CIP. Walkway and Ladder Top center None Ladder Two Stainless steel tubular with grip steps and dual large step, bolt on. Ladder Location One mounted curbside and roadside, near center of trailer. Cabinet Cabinet None. No Cabinet installed. Pump System Hydraulic Lines None Meter None Meter None Meter None Meter Installation None TANK Ai™ IntelliSECURE TANK Ai™ - None installed Miscellaneous Decals Standard warning and safety package. Decals in English. Conspicuity Tape Discontinuous tape Customer Logo None		Venti	ng and cleanouts
Cleanouts Cleanout Cleanouts Cleanouts	* Vacuum	3	Run-O-Vent in manhole cover
* Cleanouts 3" stainless steel ACME threaded ferrule with cap, nut and duscover Installed forward of the manhole. * CIP system \$Short provision for 1 1/2" top mount customer mounted CIP system. 1 1/2" mounting brackets installed for a top mount customer installed CIP. Walkway and Ladder			Installed in the manhole cover.
cover Installed forward of the manhole. *CIP system Short provision for 1 1/2" top mount customer mounted CIP system. 1 1/2" mounting brackets installed for a top mount customer installed CIP. Walkway and Ladder Top center None Ladder Ladder Two Stainless steel tubular with grip steps and dual large step, bolt on. Ladder Location One mounted curbside and roadside, near center of trailer. Cabinet None. No Cabinet installed. Pump System Hydraulic Lines None Meter None Meter None Meter Installation None TANK Ai™ IntelliSECURE TANK Ai™ - None installed Miscellaneous Decals Conspicuity Tape Discontinuous tape Customer Logo None Document holder Truck Lite 97960 Certificate Holder. Install in standard location unless otherwise specified. Calibration Computer generated theoretical calibration chart, 1/4" increments. Based on innage. Paint None. No paint or primer installed on trailer. Passivate None Warranty Polar standard two year. Tests Standard testing.	Cleanouts		None
Short provision for 1 1/2" top mount customer mounted CIP system. 1 1/2" mounting brackets installed for a top mount customer installed CIP. Walkway and Ladder Top center Ladder Ladder Top Cabinet Cabinet Cabinet None None No Cabinet installed. Pump System Hydraulic Lines Meter None Meter Installation None TANK AI™ IntelliSECURE TANK AI™ IntelliSECURE TANK AI™ Discontinuous tape Customer Logo None Calibration Calibration Calibration Calibration Calibration Computer generated theoretical calibration chart, 1/4" increments. Based on innage. Paist None Walkway and Ladder None Walkway and Ladder Top mounting brackets installed for a top mount customer mounted CIP system. None Tank AI™ Tank AI™ IntelliSECURE TANK AI™ - None installed Miscellaneous Decals Conspicuity Tape Discontinuous tape Customer Logo None Document holder Calibration Computer generated theoretical calibration chart, 1/4" increments. Based on innage. Paint None. No paint or primer installed on trailer. Passivate None Warranty Polar standard two year. Tests Standard testing.	* Cleanouts		3" stainless steel ACME threaded ferrule with cap, nut and dust cover
system. 1 1/2" mounting brackets installed for a top mount customer installed CIP. Walkway and Ladder Top center Ladder Ladder Cabinet Cabinet Cabinet None Pump System Hydraulic Lines Meter Meter None Meter Installation TANK AI™ IntelliSECURE TANK AI™ - None installed Miscellaneous Decals Conspicuity Tape Customer Logo Document holder Calibration Cabinet Computer generated theoretical calibration chart, 1/4" increments. Based on innage. Paist Paist None None None Standard two year. Tests Standard testing.			Installed forward of the manhole.
Top center Ladder Ladder Ladder Location Cabinet Cabinet Cabinet None. No Cabinet installed. Pump System Hydraulic Lines Meter None Meter None Meter Installation None TANK Ai™ IntelliSECURE TANK Ai™ Decals Conspicuity Tape Customer Logo Document holder Cabinet None None None Computer generated theoretical calibration chart, 1/4" increments. Based on innage. Passivate None None None None None None Miscellaneous Standard two year. Pasts Standard two year. Polar standard two year. Tests Standard testing.	* CIP system		system. 1 1/2" mounting brackets installed for a top mount
Ladder Location Two Stainless steel tubular with grip steps and dual large step, bolt on. Cabinet Cabinet None. No Cabinet installed. Pump System Hydraulic Lines Meter None Meter None Meter Installation None TANK Ai™ IntelliSECURE TANK Ai™ - None installed Miscellaneous Decals Conspicuity Tape Customer Logo Document holder Calibration Computer generated theoretical calibration chart, 1/4" increments. Based on innage. Paint None Passivate None None None None None None None Standard warning and safety package. Decals in English. Computer generated theoretical calibration chart, 1/4" increments. Based on innage. Paint None. No paint or primer installed on trailer. Passivate None Warranty Polar standard two year. Tests Standard testing.		Walk	way and Ladder
bolt on. One mounted curbside and roadside, near center of trailer. Cabinet None. No Cabinet installed. Pump System Hydraulic Lines None Meter None Meter None TANK Ai™ IntelliSECURE TANK Ai™ - None installed Miscellaneous Decals Casinet Standard warning and safety package. Decals in English. Conspicuity Tape Customer Logo None Truck Lite 97960 Certificate Holder. Install in standard location unless otherwise specified. Calibration Calibration Canputer generated theoretical calibration chart, 1/4" increments. Based on innage. Paint None. No paint or primer installed on trailer. Passivate None Warranty Polar standard two year. Tests Standard testing.	Top center		None
Cabinet None. No Cabinet installed. Pump System Hydraulic Lines None Meter None Meter Installation None TANK Ai™ IntelliSECURE TANK Ai™ - None installed Miscellaneous Decals Conspicuity Tape Customer Logo Document holder Calibration Calibration Camputer generated theoretical calibration chart, 1/4" increments. Based on innage. Paint None None Warranty Polar standard two year. Tests Standard testing.	Ladder		Two Stainless steel tubular with grip steps and dual large step, bolt on.
Pump System Hydraulic Lines None Meter None Meter Installation None TANK Ai™ - None installed Miscellaneous Decals Conspicuity Tape Customer Logo Document holder Calibration Calibration Calibration Polar standard warning and safety package. Decals in standard location unless otherwise specified. Computer generated theoretical calibration chart, 1/4" increments. Based on innage. Paint None None Warranty Polar standard two year. Tests Standard testing.	Ladder Location		One mounted curbside and roadside, near center of trailer.
Hydraulic Lines None Meter None Meter Installation None TANK Ai™ IntelliSECURE TANK Ai™ - None installed Miscellaneous Decals Conspicuity Tape Customer Logo Document holder Truck Lite 97960 Certificate Holder. Install in standard location unless otherwise specified. Calibration Computer generated theoretical calibration chart, 1/4" increments. Based on innage. Paint None None Warranty Polar standard two year. Tests Standard testing.			Cabinet
Hydraulic Lines Meter None Meter Installation None TANK Ai™ IntelliSECURE TANK Ai™ - None installed Miscellaneous Decals Conspicuity Tape Customer Logo Document holder Truck Lite 97960 Certificate Holder. Install in standard location unless otherwise specified. Calibration Calibration Computer generated theoretical calibration chart, 1/4" increments. Based on innage. Paint None None Warranty Polar standard two year. Tests Standard testing.	Cabinet		None. No Cabinet installed.
Meter None TANK Ai™ IntelliSECURE TANK Ai™ - None installed Miscellaneous Decals Standard warning and safety package. Decals in English. Conspicuity Tape Discontinuous tape Customer Logo None Document holder Truck Lite 97960 Certificate Holder. Install in standard location unless otherwise specified. Calibration Computer generated theoretical calibration chart, 1/4" increments. Based on innage. Paint None. No paint or primer installed on trailer. Passivate None Warranty Polar standard two year. Tests Standard testing.		P	ump System
None TANK Ai™ IntelliSECURE TANK Ai™ - None installed Miscellaneous Decals Standard warning and safety package. Decals in English. Conspicuity Tape Discontinuous tape Customer Logo None Document holder Truck Lite 97960 Certificate Holder. Install in standard location unless otherwise specified. Calibration Computer generated theoretical calibration chart, 1/4" increments. Based on innage. Paint None. No paint or primer installed on trailer. Passivate None Warranty Polar standard two year. Tests Standard testing.	Hydraulic Lines		None
IntelliSECURE TANK Ai™ - None installed Miscellaneous Decals Conspicuity Tape Customer Logo Document holder Calibration Calibration Paint Passivate Warranty Polar standard testing. TANK Ai™ - None installed Miscellaneous Standard warning and safety package. Decals in English. Discontinuous tape None None None Certificate Holder. Install in standard location unless otherwise specified. Computer generated theoretical calibration chart, 1/4" increments. Based on innage. None None None Standard two year. Standard testing.	Meter		None
TANK Ai™ - None installed Miscellaneous Decals Standard warning and safety package. Decals in English. Conspicuity Tape Discontinuous tape Customer Logo None Document holder Truck Lite 97960 Certificate Holder. Install in standard location unless otherwise specified. Calibration Computer generated theoretical calibration chart, 1/4" increments. Based on innage. Paint None. No paint or primer installed on trailer. Passivate None Warranty Polar standard two year. Tests Standard testing.	Meter Installation		None
Decals Conspicuity Tape Customer Logo Document holder Calibration Calibration Passivate Warranty Miscellaneous Standard warning and safety package. Decals in English. Discontinuous tape None Truck Lite 97960 Certificate Holder. Install in standard location unless otherwise specified. Computer generated theoretical calibration chart, 1/4" increments. Based on innage. None. No paint or primer installed on trailer. Polar standard two year. Standard testing.			TANK Ai™
Decals Conspicuity Tape Discontinuous tape Customer Logo None Truck Lite 97960 Certificate Holder. Install in standard location unless otherwise specified. Calibration Calibration Computer generated theoretical calibration chart, 1/4" increments. Based on innage. Paint None. No paint or primer installed on trailer. Passivate Warranty Polar standard two year. Tests Standard testing.	IntelliSECURE		TANK Ai™ - None installed
Conspicuity Tape Customer Logo None Document holder Calibration Calibration Paint Passivate Warranty Tests Discontinuous tape None None None Certificate Holder. Install in standard location unless otherwise specified. Computer generated theoretical calibration chart, 1/4" increments. Based on innage. None. No paint or primer installed on trailer. Polar standard two year. Standard testing.		Mi	iscellaneous
Customer Logo Document holder Truck Lite 97960 Certificate Holder. Install in standard location unless otherwise specified. Calibration Computer generated theoretical calibration chart, 1/4" increments. Based on innage. Paint None. No paint or primer installed on trailer. Passivate None Warranty Polar standard two year. Tests Standard testing.	Decals		Standard warning and safety package. Decals in English.
Document holder Truck Lite 97960 Certificate Holder. Install in standard location unless otherwise specified. Calibration Computer generated theoretical calibration chart, 1/4" increments. Based on innage. Paint None. No paint or primer installed on trailer. Passivate None Warranty Polar standard two year. Tests Standard testing.	Conspicuity Tape		Discontinuous tape
Unless otherwise specified. Calibration Computer generated theoretical calibration chart, 1/4" increments. Based on innage. Paint None. No paint or primer installed on trailer. Passivate None Warranty Polar standard two year. Tests Standard testing.	Customer Logo		None
Paint None. No paint or primer installed on trailer. Passivate None Warranty Polar standard two year. Tests Standard testing.	Document holder		Truck Lite 97960 Certificate Holder. Install in standard location unless otherwise specified.
Passivate None Warranty Polar standard two year. Tests Standard testing.	Calibration		
Warranty Polar standard two year. Tests Standard testing.	Paint		None. No paint or primer installed on trailer.
Tests Standard testing.	Passivate		None
	Warranty		Polar standard two year.
Drawings None.	Tests		Standard testing.
	Drawings		None.