



A022025 VIN: 000411

## SALES | RENTALS | PARTS | SERVICE

Allentown, PA: 800-383-8894 Jacksonville, FL: 800-828-3055 Baltimore. MD: 833-424-8944 888-601-7500 Little Rock, AR: Boston, MA: 800-854-5310 Portland, ME: 800-325-4253 Concord, NC: 800-438-2250 Richmond, VA: 866-839-3495 Delmar, DE: 866-486-1400 Scranton, PA: 800-569-1400 Des Moines, IA: 888-673-5011 Springfield, MA: 800-854-5306 Elkton, MD: Voorhees, NJ: 800-544-7127 866-315-0235

HaleTrailer.com | @haletrailer **f** 



800-232-6535

6535 \*FINANCING

Base Weight:

18,540

## 53ET3XP 53 ft. Tridem Paving & Recovery

TRAILER

Overall Length 53 ft.

Overall Width 102 in. (Over width permits may be required)

Weight lbs +/- 2% 19759, including options

\*NPO\*: King pin to center of rear axle not to exceed 42 ft 11 in.

GOOSENECK

Coupler Weld in King Pin

**Coupler Plate** 5/16 in. Hi-Tensile, 48 in. Height

Coupler Location18 in.Length10 ft. 6 in.

Cross Members Hi-Tensile 4 in. Jr. I-beam @ 16 in. O/C

Swing Clearance 83 in.

Floor 1 1/8 in. Shiplapped Apitong/Keruing

Web 1/4 in. Hi-Tensile

DECK

Deck Length35 ft. 1 in.Loaded Deck Height35 in.

Main Frame 3/8 in. x 5 in. Top Flange and 1/2 in. x 5 in. Bottom 100 KSI

Cross Members Hi-Tensile Standard 4 in. I-beam @ 12 in. O/C on Lower Deck w/ Knee Braces

Side Rail6 in. @ 8.2 ChannelWeb3/16 in. Hi-TensileLanding GearDual 2 Speed

**Floor** 1 3/8 in. Shiplapped Apitong/Keruing with 3/16 in. Deckplate over the wheels

In Floor Chain Box 1 - located at rear of Gooseneck, 1 - located at rear of main deck, with deckplate

covers included

SUSPENSION/AXLES

Axles 25,000 lbs Capacity

Air Lift c/w Control Box: lead axle

**Spread** \*NPO\*: 60 in.

Suspension Ridewell RAR 260 U/S 6 1/2 in. Air Ride 25,000 lbs - includes air gauge and dump

valve in enclosure

Brakes Quick Change 12 1/4 in. x 7 in.

Brake Chamber #3030, All Axles

Air Brake System 2S/1M
Air Tank(s) Aluminum
Slack Adjusters Automatic

Camshafts 28 Spline Non Enclosed

**Hubs & Drums** 8 Stud Unimount C / W Cast Drums

Tires Tire Upgrade to 245/70R17.5 Continental HTL2 ECO

**Tire Inflation** \*NPO\*: Meritor System, Included

Wheels Alum. Wheel Pkg. 17.5 (6 steel, 6 polished)

BEAVERTAIL

**Length** 6 ft. @ 8 degree slope, Planked

RAMPS

Rear 45 in X 11 ft. Air Operated Bi Fold - Planked

Main Deck to G/N 12 ft. Inset Full width Air Operated - Planked

Main Deck to G/N \*NPO\*: Ramp Prop Access Covers

**GENERAL SPECIFICATIONS** 

Electrical System Modular, Vapor Proof GROTE Ultra Blue

Lights LED CMVSS 108 / FMVSS 108

Front Connector SAE J560 7 Pin
Rear Connector 4 Pin Plug

Finishing Preparation by Steel Shot Blast, Commercial / Industrial Topcoat, Oven Baked

Color BWS Red - PPG#370-75034

Mudflaps 1 set of BWS at rear

**Load Securement** \* Moulded Rub Rail, Stake Pockets and Spools 24 in. OC (Over all Width affected by

option as shown)

Load Securement 15, Pair of in Floor Flush Mounted D-Rings: 3 pr GNK; 2 pr B/T; start directly after

front ramp - 10 pr main deck, evenly spaced